# GOVERNMENT OF WEST BENGAL
DIRECTORATE OF FORESTS
OFFICE OF THE DIVISIONAL FOREST OFFICER,
**PANCHET DIVISION**
*Satyajit Sarani, Bishnupur, Bankura*
*Phone & Fax No.. 03244-252189, E-mail:Panchetvp@gmail.com,*
*Website: www.bankuraforest.in*


SAVE GREEN SEE DREAM

**Quotation No.39/BLDG/TD/Gr.-C**

**Dated, Bishnupur, the:16/05/2023**

In terms of Finance Department Audit Branch Govt. of West Bengal's Memorandum No. 5400-F(Y) dated 25-06-2012 sealed quotations are invited from bonafied experienced and reliable resourceful agencies having experience in any Govt. /Semi Govt. / Govt. Under takings for providing various categories services as detailed in schedule below subject to the following conditions.Quotations should be addressed to the undersigned in sealed cover by name as well as official designation ***Sri Anjan Guha, WBFS, Divisional Forest Officer, Panchet Division, Bishnupur.***

**SCHEDULE OF WORKS RELATED TO RENOVATION WORK OF GROUP –"C" STAFF QUARTER(Qtr No. B/13/TD/PSC) AT ASNA BEAT, TALDANGRA RANGE UNDER, PANCHET DIVISION, BISHNUPUR**
**Quarter Location: Latitude- N23°02'50.95"Longitude- E87°07'00.9"**

**Estimate Copy Enclosed**

## TERMS AND CONDITIONS

1) The Quotation should be submitted in **sealed cover. Quotation No., Bidder's Name & Address should be properly mentioned on the envelope. Incomplete Quotation paper or documents or envelope will be rejected.**
2) The Contractor should **quote the rates, Percentage (%) in figures as well as in words**.
3) The materials to be supplied must be approved by the concerned Authority.
4) If any defects or issues are found with the supplied materials, they will likely need to be replaced with materials that meet the necessary standards. This is likely to ensure the safety and quality of the materials being used in whatever application they are intended for.
5) **The Contractors should submit Income-Tax, Sales Tax and profession Tax Clearance Certificate, GSTCertificate, PAN, Aadhaar& Trade License. Incomplete Quotation will be summarily rejected.**
6) Acceptance of lowest quotation is not obligatory and the undersigned reserves the right to accept or reject any of all the quotations without assigning any reason whatsoever.
7) **The estimated rate is inclusive of all Taxes, Transportation Cost to the Division Office, Panchet Division. The quotationer should quote their rate accordingly.**
8) **Bill has to be submitted with detail break up of GST (CGST & SGST) as per the prevalent Govt. Order in this respect. All Taxes will be deducted from the gross bill as per Govt. rule**.
9) Sealed Quotation will be received up **to25/05/2023& Opened on26/05/2023 at 11:30 A.M.**

Divisional Forest Officer
Panchet Division
Bishnupur Bankura

**No.** 1648(2)/02-08

**Dated, Bishnupur, the: 16/05/2023**

**Copy forwarded for information to and wide circulation to :**

1. The Divisional Forest Officer, Panchet Division, Bishnupur.
2. The Assistant Divisional Forest Officer, [illegible] Panchet Division, Bishnupur.
3. The Sub- Divisional Officer, Bishnupur.
4. The Sub- Divisional Information & Cultural Officer, Bishnupur.
5. The Block- Development Officer, Bishnupur.
6. The Chairman, Bishnupur, Municipality
7. The All Range Officers, Panchet Division with request to affix in the Range Notice board.
8. The Computer Operator to uploading 'www.bankuraforest.in' website
9. Office Notice Board.

Divisional Forest Officer
Panchet Division
*Bishnupur Bankura*

**Annexure - BL - 2**

**2406-01-070-SP-001-19-00-V**

ESTIMATE FOR REPAIR AND MINOR MAINTENANCE WORK OF GRUP-C STAFF QUARTER

( The Rate Based On P.W.D. Schedule Effected from 1st November , 2017 )

| Sl. No | Description of item | M.F. | No. | L (m.) | B (m.) | D (m.) | Quantity (m3) | Unit | Rate (Rs.) | Amount (Rs.) |
|---|---|---|---|---|---|---|---|---|---|---|
| 1 | **{ P.W.D. / Page No. 275 / Item No. 1}** | | | | | | | | | |
| | Repairing crack in wall by cement grouting (1 : 2) including widening the crack on the surface (into V section) cleaning and packing the same with cement mortar (1 : 2) and finishing off to match with adjacent surface. | | | | | | | | | |
| | | | | | | | 14.000 | | | |
| | | | | | | | 14.000 | R.M. | 13.01 | 182.14 |
| 2 | **{ P.W.D./Page No. 275/ Item No. 2(A)(ii)(a)}** | | | | | | | | | |
| | (A) Stitching crack in brick wall by carefully cutting out face brick 125 mm. deep into the wall, cleaning the gap and filling up the same with precast cement concrete block carefully set in cement mortar (1:3) including mending good damages and finishing the surface to match with adjacent areas complete as per direction | | | | | | | | | |
| | (ii) With reinforced cement concrete blocks (1:1½:3) with stone chips and nominal reinforcement. | | | | | | | | | |
| | (a) Block size 250 x 125 x 75 mm. | | | | | | | | | |
| | | | | | | | 12 | Nos | | |
| | | | | | | | 12 | NOS | 85.00 | 1,020.00 |
| 3 | **{ P.W.D./Page No. 192/ Item No. 1}** | | | | | | | | | |
| | Labour for chipping of concrete surface before taking out plaster etc. | | | | | | | | | |
| | For Roof treatment | | 1 | 6.35 | 6.35 | | 40.323 | sq.m | | |
| | | | 1 | 2.40 | 1.50 | | 3.600 | | | |
| | | | | | | | 43.923 | sq.m | 21.00 | 922.37 |
| 4 | **{P.W.D./Page No.11/Item No. 10}** | | | | | | | | | |
| | Stripping off worn out plaster and raking out joints of walls, celings etc. | | | | | | | | | |
| | Ceiling | | 1 | 3.700 | 3.050 | | 11.285 | | | |
| | Wall | | 1*2(3.70+3.05)*1.50 | | | | 20.250 | | | |
| | | | 1 | 2.550 | 2.850 | | 7.268 | | | |
| | | | 1X2(2.55+2.85)X1.00 | | | | 10.800 | | | |
| | | | 1 | 2.750 | 2.550 | | 7.013 | | | |
| | | | 1X2(2.75+2.55)X1.20 | | | | 12.720 | | | |
| | | | 1 | 2.500 | 1.800 | | 4.500 | | | |
| | | | 1X2(2.50+1.80)X1.00 | | | | 8.600 | | | |
| | | | | | | | 82.435 | sq.m | 19.00 | 1,566.27 |
| 5 | **{P.W.D./Page No.189/ Item No. 1(ii)}** | | | | | | | | | |
| | Plaster (to wall, floor, ceiling etc.) with sand and cement mortar | | | | | | | | | |
| | including rounding off or chamfering corners as directed and | | | | | | | | | |
| | **raking out joints including throating, nosing and drip course,** | | | | | | | | | |
| | **(i) With 1:6 cement mortar** | | | | | | | | | |
| | c) 15 mm thick plaster Outside Plaster | | | | | | | | | |
| | | | 1X2(3.75+3.05)X1.50 | | | | 20.400 | | | |
| | | | 1X2(2.55+2.85)X1.00 | | | | 10.800 | | | |
| | | | 1X2(2.55+2.75)X1.20 | | | | 12.720 | | | |
| | | | 1X2(2.50+1.80)X1.00 | | | | 8.600 | | | |
| | | | | | | | 52.520 | sq.m | 134.00 | 7,037.68 |
| 6 | **(ii) With 1:4 cement mortar** | | | | | | | | | |
| | (c) 10 mm thick plaster Ceiling | | | | | | | | | |
| | | | 1 | 3.700 | 3.050 | | 11.285 | | | |
| | | | 1 | 2.550 | 2.850 | | 7.268 | | | |
| | | | 1 | 2.750 | 2.550 | | 7.013 | | | |
| | | | 1 | 2.550 | 1.800 | | 4.590 | | | |
| | | | | | | | 30.156 | sq.m | 122.00 | 3,679.03 |

| | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | **{P.W.D./Page No.40/ Item No. 27(c)}** | | | | | | | | | |
| | Cement concrete 1:1.5:3 with graded stone chip 5.6 mm size with hexagonal square mesh wire netting , I.R.C. febric mesh etc.(37.5 mm thick) | | | | | | | | | |
| | Roof Treatment | | 1 | 6.350 | 5.250 | | 33.338 | | | |
| | | | 1 | 2.400 | 1.500 | | 3.600 | | | |
| | | | | | | | 36.938 | sq.m | 584.00 | 21,571.79 |
| 8 | **{P.W.D./Page No. 114 / Item No. 1(i)}** | | | | | | | | | |
| | Wood work in door,window,frame fitted and fixed etc. (i)Other Local Wood | | | | | | | | | |
| | Door | | 3 | 4.900 | 0.100 | 0.075 | 0.110 | | | |
| | Window | | 3 | 6.600 | 0.100 | 0.075 | 0.149 | | | |
| | | | | | | | 0.259 | sq.m | 36302.00 | 9,402.22 |
| 9 | **{P.W.D./Page No. 117 / Item No. 1(iii)(c)}** | | | | | | | | | |
| | Panel shutter of door and window as per design. | | | | | | | | | |
| | (iii) 35 mm thick shutters with 19 mm thick panel. | | | | | | | | | |
| | © Other Local Wood etc. | | | | | | | | | |
| | Door | | 3 | 0.775 | | 2.000 | 4.650 | | | |
| | Window | | 3 | 1.325 | | 1.075 | 4.273 | | | |
| | | | | | | | 8.923 | sqm. | 1601.00 | 14,285.72 |
| 10 | **{P.W.D./Page No.11 / Item No. 6}** | | | | | | | | | |
| | Dismelting artificial stone flooring upto 50 mm thick etc. | | 1 | 2.500 | 1.200 | | 3.000 | | | |
| | | | 1X2(2.50+1.20)X2.00 | | | | 14.800 | | | |
| | | | | | | | 17.800 | sq.m | 50.00 | 890.00 |
| 11 | **{P.W.D./Page No.48/ Item No. 6(iii)}** | | | | | | | | | |
| | Artificial stone in floor dado staircase etc. | | | | | | | | | |
| | 35mm thick (1:2:4) | | 1 | 2.500 | 1.200 | | 3.00 | | | |
| | | | 1X2(2.50+1.20)X2.00 | | | | 14.8 | | | |
| | | | | | | | 17.80 | sq.m | 328.00 | 5,838.40 |
| 12 | **{P.W.D./Page No.200/ Item No. 2.A(a)(iv)}** | | | | | | | | | |
| | (A) Painting with best quality synthetic enamel paint of approved makeand brand including smoothening surface by sand papering etc. including using of approved putty etc. on the surface, if necessary : | | | | | | | | | |
| | (a) On timber or plastered surface : With super gloss (hi-gloss) - | | | | | | | | | |
| | (iv) Two coats (with any shade except white) | | | | | | | | | |
| | Door | 2.6 | 5 | 0.90 | | 2.00 | 23.400 | | | |
| | Window | 2.6 | 5 | 1.50 | | 1.20 | 23.400 | | | |
| | | 2.6 | 1 | 1.05 | | 1.20 | 3.276 | | | |
| | | | | | | | 50.076 | sq.m | 81.00 | 4,056.16 |
| 13 | **{P.W.D./Page No. 200 / Item No. 2(A)(iv)}** | | | | | | | | | |
| | Painting with best quality synthetic enamel paint of approved make and brand etc. | | | | | | | | | |
| | (b) On Steel or other metal Surface. | | | | | | | | | |
| | (iv) Two Coats (With any shade except white) | | | | | | | | | |
| | Door | 1.00 | 1 | 1.200 | | 2.000 | 2.400 | sqm. | | |
| | Window | 1.00 | 1 | 2.500 | | 1.200 | 3.000 | | | |
| | | 1.00 | 1 | 1.650 | | 1.200 | 1.980 | | | |
| | | | | | | | 7.380 | sqm. | 79.00 | 583.02 |
| 14 | **{P.W.D./Page No.198/ Item No. 1}** | | | | | | | | | |
| | Scraping of moss , blisters etc thoroughly from exterior surface of walls etc. | | | | | | | | | |
| | outside wall | | 2 | 6.350 | | 4.000 | 50.800 | | | |
| | | | 2 | 6.350 | | 4.000 | 50.800 | | | |
| | | | | | | | 101.600 | Cum | 7.00 | 711.20 |

| | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | **{P.W.D./Page No.194/ Item No. 1(B)}** White washing including cleaning and smoothening surface throughly. (b) Two Coats | | 1 | 3.700 | 3.050 | | 11.285 | | | |
| | | | 1x2(3.70+3.05)x3.00 | | | | 40.500 | | | |
| | | | 1 | 2.550 | 2.850 | | 7.268 | | | |
| | | | 1x2(2.55+2.85)x3.00 | | | | 32.400 | | | |
| | | | 1 | 2.550 | 2.750 | | 7.013 | | | |
| | | | 1x2(2.55+2.75)x3.00 | | | | 31.800 | | | |
| | | | 1 | 3.050 | 2.500 | | 7.625 | | | |
| | | | 1x2(3.05+2.50)x3.00 | | | | 33.300 | | | |
| | | | 1 | 2.500 | 1.200 | | 3.000 | | | |
| | | | 1x(2.50+1.20)x3.00 | | | | 22.200 | | | |
| | | | | | | | 196.391 | Sqm | 18.14 | 3,562.53 |
| 16 | **{P.W.D./Page No.200/ Item No. 1(a)}** Priming one coat on timber or plaster surface etc. (a) One Coat | | | | | | 18.720 | | | |
| | | | | | | | 18.720 | | | |
| | Door | 2.6 | 4 | 0.90 | | 2.00 | | | | |
| | Window | 2.6 | 4 | 1.50 | | 1.20 | | | | |
| | | | | | | | 37.440 | Sqm | 38.00 | 1,422.72 |
| 17 | **{P.W.D./Page No.197/ Item No. 15(iii)}** Applying decorative cement based paint of approved quality (iii) Two Coats | | | | | | | | | |
| | | | 2 | 7.35 | | 4.50 | 66.150 | | | |
| | | | 2 | 7.35 | | 4.50 | 66.150 | | | |
| | | | | | | | 132.300 | Sqm | 49.00 | 6,482.70 |
| | | | | | | | | | **Total** | **83,213.95** |
| | | | | | | | | | **Add @18% for G.S.T.** | **14,978.51** |
| | | | | | | | | | **Sub Total** | **98,192.46** |
| | | | | | | | | | **Add @1% for Cess** | **981.92** |
| | | | | | | | | | **GRAND TOTAL** | **99,174.38** |
| | | | | | | | | | **Say** | **99,174.00** |

**Ninety Nine Thousand One Hundred Seventy Four Only**

**Divisional Forest Officer**
**Panchet Division**
**Bishnupur**