



GOVERNMENT OF WEST BENGAL  
DIRECTORATE OF FORESTS  
OFFICE OF THE DIVISIONAL FOREST OFFICER,  
PANCHET DIVISION

Satyajit Sarani, Bishnupur, Bankura  
Phone & Fax No.. 03244-252189, E-mail: [Panchetup@gmail.com](mailto:Panchetup@gmail.com),  
Website: [www.bankuraforest.in](http://www.bankuraforest.in)



Quotation No. 52/BLDG/TD/Gr.-D(2<sup>nd</sup> Call)

Dated, Bishnupur, the: 31/07/2023

In terms of Finance Department Audit Branch Govt. of West Bengal's Memorandum No. 5400-F(Y) dated 25-06-2012 and 3103-F(Y) dated 27-07-2022 sealed quotations are invited from bonafied experienced and reliable resourceful agencies having experience in any Govt. /Semi Govt. / Govt. Under takings for providing various categories services as detailed in schedule below subject to the following conditions. Quotations should be addressed to the undersigned in sealed cover by name as well as official designation **Sri Anjan Guha, WBFS, Divisional Forest Officer, Panchet Division, Bishnupur.**

**SCHEDULE OF WORKS RELATED TO RENOVATION WORK OF GROUP –“D” STAFF  
QUARTER (QUARTER NO. B/21/TD-PSC) AT PANCHMURA BEAT, TALDANGRA RANGE  
UNDER PANCHET DIVISION, BISHNUPUR**

**Quarter Location: Latitude-N22°98'13.05" & Longitude-E87°10'04.03"**

**Estimate Copy Enclosed**

**TERMS AND CONDITIONS**

- 1) The Quotation should be submitted in sealed cover. Quotation No., Bidder's Name & Address should be properly mentioned on the envelope. Incomplete Quotation paper or documents or envelope will be rejected.
- 2) The Contractor should quote the rates, Percentage (%) in figures as well as in words.
- 3) The materials to be supplied must be approved by the concerned Authority.
- 4) If any defects or issues are found with the supplied materials, they will likely need to be replaced with materials that meet the necessary standards. This is likely to ensure the safety and quality of the materials being used in whatever application they are intended for.
- 5) The Contractors should submit Income-Tax, Sales Tax and profession Tax Clearance Certificate, GST Certificate, PAN, Aadhaar & Trade License. Incomplete Quotation will be summarily rejected.
- 6) Acceptance of lowest quotation is not obligatory and the undersigned reserves the right to accept or reject any of all the quotations without assigning any reason whatsoever.
- 7) The estimated rate is inclusive of all Taxes, Transportation Cost to the Division Office, Panchet Division. The quotationer should quote their rate accordingly.
- 8) Bill has to be submitted with detail break up of GST (CGST & SGST) as per the prevalent Govt. Order in this respect. All Taxes will be deducted from the gross bill as per Govt. rule.
- 9) Sealed Quotation will be received up to 08/08/2023 & Opened on 09/08/2023 at 11:30 A.M.

No. 2599(9)/02-08

Divisional Forest Officer  
Panchet Division, Bishnupur  
Dated, Bishnupur, the: 31/07/2023

**Copy forwarded for information to and wide circulation to:**

1. The Divisional Forest Officer, Panchet Division, Bishnupur.
2. The Assistant Divisional Forest Officer, Panchet Division, Bishnupur.
3. The Sub- Divisional Officer, Bishnupur.
4. The Sub- Divisional Information & Cultural Officer, Bishnupur.
5. The Block- Development Officer, Bishnupur.
6. The Chairman, Bishnupur, Municipality
7. The All Range Officers, Panchet Division with request to affix in the Range Notice board.
8. The Computer Operator to upload in '[www.bankuraforest.in](http://www.bankuraforest.in)' website
9. Office Notice Board.

Divisional Forest Officer  
Panchet Division, Bishnupur



**ESTIMATE FOR REPAIRING & MAINTENANCE WORKS OF GROUP (D) QUARTER - SOUTH BENGAL**

Sl. No.	PWD Sch. Rate Page No.	Particulars of Work	Unit	Qty.	Rate (in Rs.)	Amount (in Rs.)
1	P-11/6	a)Dismantling of damaged existing concrete roof - [(3.80x4.30)+(3.70x4.50)+(3.80x1.30)+(4.20x3.10)] = 50.95m <sup>2</sup>	m <sup>2</sup>	50.950	50.00	2,547.50
2	P-35/23(3)	Water proof treatment for roof protection (skid concrete) 50mm thick (1:1.5:3) with all approved required metatials full complete. [(3.80x4.30x0.05)+(3.70x4.50x0.05)+(3.80x1.30x0.05)+(4.20x3.10x0.05)] = 2.547m <sup>2</sup>	m <sup>3</sup>	2.547	5725.67	14,583.28
3	P-11/10	Dismantling damaged plastering inside wall, outside wall, ceiling etc. Area approx: 119 m <sup>2</sup>	m <sup>2</sup>	119.000	19.00	2,261.00
4	P-189/1(i)(b)	20mm (1:6) plastering to wall- [(5.80x4.00)+(3.20x4.20)+(5.50x1.20)+(3.50x2.20)]=50.94m <sup>2</sup> Damaged plaster wall ceiling- L.S- 35.0m <sup>2</sup> (50.94+35.0)=85.94m <sup>2</sup>	m <sup>2</sup>	85.94	152.00	13,062.88
5	P-16/16	125 thick brick work(1:4) above (average height 1.25m) - 6.09 x 1.20 = 7.308 m <sup>2</sup>	m <sup>2</sup>	7.308	660.00	4,823.28
6	P-200/I(b)	Decorative priming(one coat) internal wall/ceiling of - [(5.80x4.00)+(3.20x4.20)+(5.50x1.20)+(3.50x2.20)]=103.64m <sup>2</sup> Ceiling- 35.00m <sup>2</sup> (3.70x4.50)=16.65m <sup>2</sup> (2.50x3.80)=09.50m <sup>2</sup> (3.80x1.30)=04.94m <sup>2</sup> (7.60x4.20)=31.92m <sup>2</sup> Total=63.01m <sup>2</sup> Grand total= (103.64+35.00+63.01)=201.65m <sup>2</sup>	m <sup>2</sup>	201.650	29.00	5,847.85
7	P-193/15(iii)	Decorative paint(two coat) internal wall/ceiling of - [(5.80x4.00)+(3.20x4.20)+(5.50x1.20)+(3.50x2.20)]=50.94m <sup>2</sup> Ceiling- 35.00m <sup>2</sup> (3.70x4.50)=16.65m <sup>2</sup> (2.50x3.80)=09.50m <sup>2</sup> (3.80x1.30)=04.94m <sup>2</sup> (7.60x4.20)=31.92m <sup>2</sup> Total=63.01m <sup>2</sup> Grand total= (103.64+35.00+63.01)=201.65m <sup>2</sup>	m <sup>2</sup>	201.650	49.00	9,880.85
8	P-192/15	Neat cement finish- 8.20x4.23=34.70m <sup>2</sup>	m <sup>2</sup>	34.700	38.00	1,318.60
9	P-89/7	MCB Enclosure 2 way	Each	6.000	220.00	1,320.00
10	P-89/49	PVC Casing capping of size 25x12mm	m	44.000	27.07	1,191.08
11	P-90/70	1.5 sqmm 'FR' stranded copper wire	m	120.000	13.68	1,641.60
12	P-90/70	6 module GI box	Each	4.000	102.00	408.00

